


# 17663

17660

QB2 WITH 4" MICROFLASHING®  
FOR ASPHALT, EPDM, & TPO ROOFS  
PATENT # 8448407



A DIVISION OF QUICKSCREWS INTERNATIONAL CORP

# TABLE OF CONTENTS

3

## SPEC SHEET

QTY & MEASUREMENT INFORMATION

---

5

## UL CERTIFICATION

PROOF OF UL CERTIFICATION

---

7

## INSTALLATION INSTRUCTIONS

STEP-BY-STEP-INSTALLATION GUIDE

---

10

## BUILDING CODE LETTER

REGARDING STAMP DATES

---

11

## ENGINEERING REPORT

UPLIFT & LATERAL LOAD TEST

---

19

## CHEMLINK COMPATIBILITY LETTER

OPTIONAL SEALANT

---

20

## MIAMI-DADE NOA

MIAMI-DADE FLORIDA APPROVAL

---


# SPEC SHEET

| Part # | Box Quantity                                     |
|--------|--------------------------------------------------|
| 17660  | 4" QB2 (25)                                      |
| 17663  | 4" Microflashing® (25); 4" QB2 (25); L-Foot (25) |




**QB2**

PN# 17660




Dual Drive Technology  
1/2" Hex Outer Drive  
6mm Inner Drive



|                                   |  |             |            |                                       |
|-----------------------------------|--|-------------|------------|---------------------------------------|
| MATERIAL:<br>Stainless Steel 304  |  | QuickBOLT   |            |                                       |
| SURFACE TREATMENT:<br>PASSIVATION |  | NAME:       | DATE:      | STATUS: Approved                      |
|                                   |  | DRAWN:      | MAR. 19'19 | ITEM: 5/16 X 4" HEX FLANGE QUICK BOLT |
|                                   |  | APPROVED:   | MAR. 19'19 | DRAWING NO. SL20190316-1              |
| TOLERANCE:<br>AS PER DRAWING      |  | VERSION: 01 | FORMAT: A3 | Scale: 5:1                            |
|                                   |  | ISO:        | PAGES: 1/1 | UNIT: METRIC                          |
|                                   |  | SALES:      |            |                                       |

PN# 17661  
L-Foot for QB2



Part # 17659

5/16" x 4"  
304 Stainless Steel  
**Compression Washer Black**



## CERTIFICATE OF COMPLIANCE

**Certificate Number** E493748  
**Report Reference** E493748-20170817  
**Date** 2023-April-07

**Issued to:** QuickBOLT a Division of Quickscrews International Corp  
5830 Las Positas Rd  
Livermore CA, 94551 US

**This is to certify that  
representative samples of**

MOUNTING SYSTEMS, MOUNTING DEVICES, CLAMPING  
DEVICES AND GROUND LUGS FOR USE WITH  
PHOTOVOLTAIC MODULES AND PANELS - COMPONENT

See Addendum Page for Product Designation(s).

Have been evaluated by UL in accordance with the component  
requirements in the Standard(s) indicated on this Certificate. UL  
Recognized components are incomplete in certain constructional  
features or restricted in performance capabilities and are  
intended for installation in complete equipment submitted for  
investigation to UL LLC.

**Standard(s) for Safety:** UL 2703, Mounting systems, mounting devices,  
clamping/retention devices, and ground lugs for use with flat-  
plate photovoltaic modules and panels-.

**Additional Information:** See the UL Online Certifications Directory at  
<https://iq.ulprospector.com> for additional information

This Certificate of Compliance indicates that representative samples of the product described in the certification  
report have met the requirements for UL certification. It does not provide authorization to apply the UL  
Recognized Component Mark. Only the Authorization Page that references the Follow-Up Services Procedure  
for ongoing surveillance provides authorization to apply the UL Mark.

Only those products bearing the UL Recognized Component Mark should be considered as being UL Certified  
and covered under UL's Follow-Up Services.

Look for the UL Recognized Component Mark on the product.

  
Deborah Jennings-Conner, VP Regulatory Services  
UL LLC

Any information and documentation involving UL Mark services are provided on behalf of UL LLC (UL) or any authorized licensee of UL. For questions, please  
contact a local UL Customer Service Representative at <http://ul.com/aboutul/locations/>



# CERTIFICATE OF COMPLIANCE

**Certificate Number** E493748  
**Report Reference** E493748-20170817  
**Date** 2023-April-07

This is to certify that representative samples of the product as specified on this certificate were tested according to the current UL requirements

## Models:

USR – Component, Roof Mounting Hook Units, Models 15891 15893 15987 16000 16317 16318 16319 16320 16988 16990 16991 16993 17508 17509 17510 17511 17512 17513 17514 17515 17516 17517 17518 17519 17520 17521 17522 17523 17524 17525 17526 17527 17536 17537 17538 17539 17540 17541 17542 17543 17544 17545 17546 17547 17548 17549 17550 17551 17552 17553 17554 17555 17556 17558 17559 17560 17566 17567 17568 17569 17570 17571 17572 17573 17574 17575 17576 17577 17578 17579 17580 17585 17586 17587 17588 17589 17592 17596 17597 17598 17599 17600 17601 17606 17607 17608 17609 17610 17611 17612 17613 17614 17615 17616 17617 17618 17620 17621 17622 17623 17624 17625 17626 17627 17628 17629 17630 17631 17632 17633 17636 17637 17638 17639 17640 17641 17642 17643 17646 17647 17648 17649 17650 17651 17652 17653 17654 17659 17664 17667 17669 17670 17671 17672 17673 17678 17679 17680 17681 17686 17687 17688 17689 17700 17701 17702 17703 17704 17705 17706 17707 17708 17709 17710 17711 17712 17717 17718 17750 17751 17752 17753 17759 15891-10 15891BLK-10 15987A 15987B 17667SS 17672SS 17680SS 17688SS 17713SS 17720 17721SS 17723 17724SS 17726 17727SS 17729 17730SS 15894SS 15891SS 15987BSS 17660 17661 17662 17663 17747 17748

*Deborah Jennings-Conner*

Deborah Jennings-Conner, VP Regulatory Services

UL LLC

Any information and documentation involving UL Mark services are provided on behalf of UL LLC (UL) or any authorized licensee of UL. For questions, please contact a local UL Customer Service Representative at <http://ul.com/aboutul/locations/>



# INSTALL INSTRUCTIONS

## QB2 (17662)

### RECOMMENDED MATERIALS

- Tools to locate and mark rafter
- Drill with a 15/64" drill bit
- MFG approved sealant (optional)
- 1/2" Nut Setter

### INSTALLATION INSTRUCTIONS

1. Locate and mark the rafter
2. Predrill the hole
3. Optional: Fill the predrilled hole with MFG approved sealant
4. Optional: Place a ring of sealant around the bottom of the Microflashing® washer
5. Place the Microflashing®
6. Insert the Bolt into the L-Foot
7. Drive the Bolt until the Microflashing® is compressed

---

Use a minimum torque of **150 in-lbs** to properly compress Microflashing® when installing QB2.

The Bolt will compress the Microflashing® and when fully compressed the L-Foot will not rotate.



1



2



3




4



5



6



7



# INSTALL INSTRUCTIONS CONT.

## CRITICAL PLACEMENT: BUTT JOINTS & KEYWAYS

The Microflashing® must be evenly compressed against the shingle surface to seal correctly. At most installations points this occurs normally. However, extra care is required when the mounting location falls over a butt joint or keyway (ridges or gaps in the shingle surface).

The installer is responsible for determining the best method to create a flat, even surface for the Microflashing®, either by adjusting mount location or addressing the shingle condition as appropriate.

## SHINGLE OVERLAPS & RIDGES

- Do not place the Microflashing® directly over butt edges or overlapping shingles.
- Edge overlaps create ridges that prevent even compression.

### Preferred approach:

Whenever possible, adjust the mount location up or down so the Microflashing® can sit fully flush on a flat shingle surface, either below the edge/overlap or fully onto the upper shingle, allowing the entire flashing to seat evenly.

### If the mount location cannot be moved:

The installer must determine the best method to create a flat, supported surface. Options to consider include:

- Add sealant above the mount — when installing where two shingles meet, add a bead of sealant in the gap between the shingles on the sky-side (the uphill side) of where the Microflashing® will sit. This ensures water sheds properly above the mount.
- Sliding the Microflashing® under the upper shingle, or
- Trimming the shingle as needed so the Microflashing® can sit flat and fully supported.



# INSTALL INSTRUCTIONS CONT.

## KEYWAYS (3-TAB SHINGLES), GAPS AND CHANNELS

- Do not span a keyway gap or butt joint channel with the Microflashing®.
- Keyways and channels are designed to shed water and must remain open to function correctly.

### **Preferred approach:**

Whenever possible, adjust the mount location so the Microflashing® sits entirely on solid shingle, clear of a channel, allowing full, even compression.

### **If the mount location cannot be moved:**

The installer must determine the best method to create a flat, supported surface. Options to consider include:

- Sealing the channel to create a continuous surface even with the surrounding shingles, then installing the Microflashing® flat over the sealed area.

## ENSURING PROPER COMPRESSION

- Use the torque specified on page 7 to ensure the fastener is fully compressed
- The Microflashing® should always form a smooth, even concave shape with no gaps, lifting, or uneven deformation around its outer edge.



# BUILDING CODE LETTER



March 22<sup>nd</sup>, 2023

To whom this may concern,

QuickBOLT is committed to excellence. The parts tested are durable goods, meaning the material composition and detailed specifications of the parts do not change. Therefore, all stamps are current. Any part tested will have the same results no matter what year the tests are performed. All testing and reports are current and valid with 2022 CBC standards.

SolarRoofHook is the previous name of QuickBOLT. Any test result referencing SolarRoofHook is referring to a QuickBOLT product.

All our parts were tested by a third-party test facility, in possession of a current engineering license for the state where the tests were performed for the following.

1. Uplift test
2. Downward load test
3. Lateral Test – Asphalt Mounts, and Metal Mounts only
4. ASTM E2440 and ASTM E330 Waterproof Tests - QuickBOLT only

The following is an excerpt from:

CALIFORNIA BOARD FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS  
guide to Engineering & Land Surveying for City and County Officials  
Page 12, Line 27

**27. If the license has expired between the time the engineering documents were prepared and the time when the local agency's review is performed, do the documents need to be re-sealed by a licensee with a current license? (B&P Code §§ 6733, 6735, 6735.3, 6735.4)**

**As long as the license was current at the time the engineering documents were prepared, the documents do not need to be re-sealed prior to review by the local agency. However, any changes (updates or modifications) to the documents that are made following the review by the local agency would have to be prepared by a licensed engineer with a current license and those changes would have to be signed and sealed.**

We trust the information provided will resolve any request for the test reports submitted to have a stamp from the current year.

Regards,

Rick Gentry  
Executive Vice President

# ENGINEERING REPORT



## QUICKSCREWS INTERNATIONAL CORP. MOCK-UP TEST REPORT

### SCOPE OF WORK

UPLIFT AND LATERAL LOAD TEST FOR QB2 QUICKBOLT

Part# 17662 – 4.00" QB2 Kit 3" Microflashing® + SS-LFT 25/KTP

Part# 17663 – 4.00" QB2 Kit 4" Microflashing® + SS-LFT 20/KTP

### REPORT NUMBER

K3215.01-301-44

### TEST DATES

10/30/19 - 10/31/19

### ISSUE DATE

12/06/19

### REVISION 1 DATE

12/19/19

### RECORD RETENTION END DATE

10/31/24

### PAGES

10

### DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-2744 (04/05/18)

© 2017 INTERTEK



**TEST REPORT FOR QUICKSCREWS INTERNATIONAL CORP.**

Report No.: K3215.01-301-44


Date: 12/06/19

**REPORT ISSUED TO**

QuickBOLT - A Division of  
QUICKSCREWS INTERNATIONAL CORP.  
5830 Las Positas Road  
Livermore, California 94551

**PROJECT**


UPLIFT AND LATERAL TEST



For INTERTEK B&C:

**COMPLETED BY:** Ricardo Cortez

**TITLE:** Technician


**SIGNATURE:** 

**DATE:** 12/19/19

RC:ms

**REVIEWED BY:** Tyler Westerling, P.E.

**TITLE:** Senior Project Engineer

**SIGNATURE:** 

**DATE:** 12/19/19

**TEST REPORT FOR QUICKSCREWS INTERNATIONAL CORP.**

Report No.: K3215.01-301-44

Date: 12/06/19

**SECTION 1**

**SCOPE**

Intertek Building & Construction (B&C) was contracted by QuickBOLT to perform performance testing on the QB2 Asphalt Mount at the Intertek B&C test facility in Fresno, CA. Results obtained are tested values. This report includes complete written and photographic documentation of all testing performed and a copy of "As-Built" mock-up drawings.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. This report and related test records that are retained such as "As-Built" mock-up drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be serviced by Intertek B&C for the entire test record retention period. At the end of this retention period, such materials shall be discarded without notice and the service life of this report by Intertek B&C will expire.

**SECTION 2**

**TEST METHOD**

Mock-up testing was performed in accordance with referenced test methods as specified in the bid documents.

**SECTION 3**

**LIST OF OFFICIAL OBSERVERS**

| NAME                   | COMPANY      |
|------------------------|--------------|
| Dustin Harris          | Intertek B&C |
| Meng Vang              | Intertek B&C |
| Tyler Westerling, P.E. | Intertek B&C |

**SECTION 4**

**GENERAL MOCK-UP DESCRIPTION**

**Uplift and Lateral Load Test**

**Material Source/Installation**

The mock-up materials/components were supplied by QuickBOLT. The installation of the mock-up was completed by Intertek B&C.

**TEST REPORT FOR QUICKSCREWS INTERNATIONAL CORP.**

Report No.: K3215.01-301-44



Date: 12/06/19

**SECTION 5**

**FINAL TEST RESULTS**

Charts below represent Uplift and Lateral loads.



| Uplift    |           | Lateral   |         |
|-----------|-----------|-----------|---------|
| Run #     | Lbf       | Run #     | Lbf     |
| #1        | 1,405     | #1        | 475     |
| #2        | 1,503     | #2        | 498     |
| #3        | 1,845     | #3        | 501     |
| #4        | 1,984     | Average = | 491 lbf |
| #5        | 2,113     |           |         |
| Average = | 1,770 lbf |           |         |



**TEST REPORT FOR QUICKSCREWS INTERNATIONAL CORP.**

Report No.: K3215.01-301-44



Date: 12/06/19



**TEST REPORT FOR QUICKSCREWS INTERNATIONAL CORP.**

Report No.: K3215.01-301-44



Date: 12/06/19



**TEST REPORT FOR QUICKSCREWS INTERNATIONAL CORP.**

Report No.: K3215.01-301-44

Date: 12/06/19



**TEST REPORT FOR QUICKSCREWS INTERNATIONAL CORP.**

Report No.: K3215.01-301-44

Date: 12/06/19

**SECTION 6**  
**CONCLUSION**

The mock-up met the specified performance requirements.

# CHEMLINK COMPATIBILITY



February 15, 2023

ATTN: Rick Gentry, Executive VP

QuickBolt

5830 Las Positas Blvd.

Livermore, California 94551

Subject: Product compatibility:

This letter is regarding the compatibility of the ChemLink M-1® Universal Adhesive and Sealant with the Microflashing® by QuickBolt. My testing indicated that there are no known compatibilities issues with Microflashings® and M-1® when they are used as directed. Acceptable adhesion was achieved within seven days of application. The M-1® adhesive / sealant was applied at 70° fahrenheit and 50% percent relative humidity.

All surfaces should be clean, dry, and free of all contaminates. Use isopropyl alcohol to prepare surfaces. Do not use mineral spirits or xylene.

Thank you,

Rick Berthiaume

Technical Services Manager

---

353 E LYONS STREET SCHOOLCRAFT, MICHIGAN 48087 PH 268.879.4440 TOLL FREE 800.826.1681 FAX 268.879.4448 WWW.CHEMLINK.COM

# MIAMI-DADE NOA



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)  
BOARD AND CODE ADMINISTRATION DIVISION  
**NOTICE OF ACCEPTANCE (NOA)**

MIAMI-DADE COUNTY  
PRODUCT CONTROL SECTION  
11805 SW 26 Street, Room 208  
Miami, Florida 33175-2474  
T (786) 315-2590 F (786) 315-2599  
[www.miamidade.gov/economy](http://www.miamidade.gov/economy)

**Quickscrews Int'l Corp.**  
**5830 Las Positas Rd.**  
**Livermore, CA 94551**

**SCOPE:**

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

**DESCRIPTION: Quick Bolt QB2 Stainless Steel L-Foot and 3" Microflashing Solar Mount**

**APPROVAL DOCUMENT:** Drawing No. **QB2HVVHZ**, titled "QB2 Kit with SS L-Foot and 3" Microflashing", sheets 1 through 2 of 2, prepared by QuikBolt a div of Quickscrews Int'l Corp., dated on 02/24/2024, signed and sealed by Scott Wolters, P.E., bearing the Miami-Dade County Product Control revision stamp with the Notice of Acceptance number and approval date by the Miami-Dade County Product Control Section.

**MISSILE IMPACT RATING: None**

**LABELING:** Each box shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved or MDCPCA", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises NOA # 22-0214.03** and consists of this page 1, evidence page E-1, as well as approval document mentioned above.

The submitted documentation was reviewed by **Carlos M. Utrera, P.E.**



04/09/24

**NOA No: 24-0306.05**  
**Expiration Date: June 23, 2027**  
**Approval Date: April 18, 2024**  
**Page 1**

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**1. Evidence submitted under NOA # 22-0214.03 and new**

**A. DRAWINGS**

1. Drawing No. **QB2HVVHZ**, titled "QB2 Kit with SS L-Foot and 3" Microflashing", sheets 1 through 2 of 2, prepared by QuikBolt a div of Quickscrews Int'l Corp., dated on 02/24/2024, signed and sealed by Scott Wolters, P.E.

**B. TESTS "*Submitted under NOA # 22-0214.03*"**

1. Test report on Uplift and Shear Allowable Loads of the 4" SS QB2 Kit w/ 3" Microflashing Solar Mount per ASTM D7147-11, prepared by Intertek, Test Report No. **K8370.01-301-18 R1**, dated 06/04/2020, with revision 1 dated 05/10/2022, signed and sealed by Tyler Westerling, P.E.
2. Test report on Wind Driven Rain Resistance of the 4" SS QB2 Kit w/ 3" Microflashing Solar Mount per TAS 100(A)-95, prepared by Intertek, Test Report No. **K8370.02-301-18 R0**, dated 06/04/2020, signed and sealed by Tyler Westerling, P.E.

**C. CALCULATIONS "*Submitted under NOA # 22-0214.03*"**

1. Anchor calculations prepared by Scott Wolters, dated 01/28/2022, signed and sealed by Scott Wolters, P.E.

**D. MATERIAL CERTIFICATIONS**

1. None.

**E. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

**F. STATEMENTS**

1. Statement letter of code conformance to the 8<sup>th</sup> edition (2023) of the FBC, issued by Wolters Engineering, dated 02/24/2024, signed and sealed by Scott Wolters, P.E.

***"Submitted under NOA # 22-0214.03"***

2. Drawing statement of code conformance to the 7<sup>th</sup> edition (2020) of the FBC issued by QuikBolt a div of Quickscrews Int'l Corp., dated 01/28/2022, signed and sealed by Scott Wolters, P.E. on 05/26/2022
3. Statement letter of no financial interest issued by Wolters Engineering, dated 01/31/2022, signed and sealed by Scott Wolters, P.E.




**Carlos M. Utrera, P.E.**  
**Product Control Examiner**  
**NOA No: 24-0306.05**  
**Expiration Date: June 23, 2027**  
**Approval Date: April 18, 2024**

## QB2 ANCHOR BRACKET SYSTEM WITH 3" MICROFLASHING.

### GENERAL NOTES:

1. THIS SYSTEM HAS BEEN DESIGNED AND TESTED TO MEET ALL OF THE REQUIREMENTS OF THE 8TH EDITION (2023) FLORIDA BUILDING CODE, INCLUDING THE HVHZ PROVISIONS.
2. THIS SYSTEM HAS BEEN TESTED PER TAS 100(A) AND ASTM D7147.
3. THE DESIGN OF THE SUBSTRATE IS THE RESPONSIBILITY OF THE ENGINEER OF RECORD OR OTHER SPECIALTY ENGINEER, AND IS NOT A PART OF THIS APPROVAL. THE SUBSTRATE MUST SAFELY TRANSMIT THE LOADS APPLIED TO THIS SYSTEM TO THE BUILDING STRUCTURE.
4. FIRE RATINGS OR FIRE RESISTANCE IS NOT A PART OF THIS REVIEW.
5. ALL ANCHORS SECURING THE SYSTEM TO PRESSURE TREATED WOOD SHALL BE CAPABLE OF RESISTING CORROSION CAUSED BY THE CHEMICALS IN THE WOOD.
6. MATERIALS INCLUDING BUT NOT LIMITED TO STEEL/METAL SCREWS THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL BE PROTECTED PER FBC REQUIREMENTS.
7. NO INCREASE IN ALLOWABLE STRESS HAS BEEN USED IN THE DESIGN OF THIS PRODUCT.  $C_d=1.6$  WAS USED FOR WOOD SCREWS ONLY.
8. VALUES SHOWN FOR THE ALLOWABLE LOADS ARE BASED ON THE QB2 MOUNTING SCREW INSTALLED WITH 3" MIN EMBEDMENT, 5/8" MIN EDGE DISTANCE, AND 2 1/2" MIN. END DISTANCE.



**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. **24-0306.05**  
Expiration Date **06/23/2027**  
By *[Signature]*  
Miami-Dade Product Control


| REV.# | DATE    | REV.# | DATE    |
|-------|---------|-------|---------|
| 1     | 1/28/22 | 2     | 2/24/24 |
| 2     | 1/28/22 | 3     | 2/24/24 |
| 3     | 1/28/22 | 4     | 2/24/24 |
| 4     | 1/28/22 | 5     | 2/24/24 |
| 5     | 1/28/22 | 6     | 2/24/24 |
| 6     | 1/28/22 | 7     | 2/24/24 |
| 7     | 1/28/22 | 8     | 2/24/24 |
| 8     | 1/28/22 | 9     | 2/24/24 |
| 9     | 1/28/22 | 10    | 2/24/24 |
| 10    | 1/28/22 | 11    | 2/24/24 |
| 11    | 1/28/22 | 12    | 2/24/24 |
| 12    | 1/28/22 | 13    | 2/24/24 |
| 13    | 1/28/22 | 14    | 2/24/24 |
| 14    | 1/28/22 | 15    | 2/24/24 |
| 15    | 1/28/22 | 16    | 2/24/24 |
| 16    | 1/28/22 | 17    | 2/24/24 |
| 17    | 1/28/22 | 18    | 2/24/24 |
| 18    | 1/28/22 | 19    | 2/24/24 |
| 19    | 1/28/22 | 20    | 2/24/24 |
| 20    | 1/28/22 | 21    | 2/24/24 |
| 21    | 1/28/22 | 22    | 2/24/24 |
| 22    | 1/28/22 | 23    | 2/24/24 |
| 23    | 1/28/22 | 24    | 2/24/24 |
| 24    | 1/28/22 | 25    | 2/24/24 |
| 25    | 1/28/22 | 26    | 2/24/24 |
| 26    | 1/28/22 | 27    | 2/24/24 |
| 27    | 1/28/22 | 28    | 2/24/24 |
| 28    | 1/28/22 | 29    | 2/24/24 |
| 29    | 1/28/22 | 30    | 2/24/24 |
| 30    | 1/28/22 | 31    | 2/24/24 |
| 31    | 1/28/22 | 32    | 2/24/24 |
| 32    | 1/28/22 | 33    | 2/24/24 |
| 33    | 1/28/22 | 34    | 2/24/24 |
| 34    | 1/28/22 | 35    | 2/24/24 |
| 35    | 1/28/22 | 36    | 2/24/24 |
| 36    | 1/28/22 | 37    | 2/24/24 |
| 37    | 1/28/22 | 38    | 2/24/24 |
| 38    | 1/28/22 | 39    | 2/24/24 |
| 39    | 1/28/22 | 40    | 2/24/24 |
| 40    | 1/28/22 | 41    | 2/24/24 |
| 41    | 1/28/22 | 42    | 2/24/24 |
| 42    | 1/28/22 | 43    | 2/24/24 |
| 43    | 1/28/22 | 44    | 2/24/24 |
| 44    | 1/28/22 | 45    | 2/24/24 |
| 45    | 1/28/22 | 46    | 2/24/24 |
| 46    | 1/28/22 | 47    | 2/24/24 |
| 47    | 1/28/22 | 48    | 2/24/24 |
| 48    | 1/28/22 | 49    | 2/24/24 |
| 49    | 1/28/22 | 50    | 2/24/24 |
| 50    | 1/28/22 | 51    | 2/24/24 |
| 51    | 1/28/22 | 52    | 2/24/24 |
| 52    | 1/28/22 | 53    | 2/24/24 |
| 53    | 1/28/22 | 54    | 2/24/24 |
| 54    | 1/28/22 | 55    | 2/24/24 |
| 55    | 1/28/22 | 56    | 2/24/24 |
| 56    | 1/28/22 | 57    | 2/24/24 |
| 57    | 1/28/22 | 58    | 2/24/24 |
| 58    | 1/28/22 | 59    | 2/24/24 |
| 59    | 1/28/22 | 60    | 2/24/24 |
| 60    | 1/28/22 | 61    | 2/24/24 |
| 61    | 1/28/22 | 62    | 2/24/24 |
| 62    | 1/28/22 | 63    | 2/24/24 |
| 63    | 1/28/22 | 64    | 2/24/24 |
| 64    | 1/28/22 | 65    | 2/24/24 |
| 65    | 1/28/22 | 66    | 2/24/24 |
| 66    | 1/28/22 | 67    | 2/24/24 |
| 67    | 1/28/22 | 68    | 2/24/24 |
| 68    | 1/28/22 | 69    | 2/24/24 |
| 69    | 1/28/22 | 70    | 2/24/24 |
| 70    | 1/28/22 | 71    | 2/24/24 |
| 71    | 1/28/22 | 72    | 2/24/24 |
| 72    | 1/28/22 | 73    | 2/24/24 |
| 73    | 1/28/22 | 74    | 2/24/24 |
| 74    | 1/28/22 | 75    | 2/24/24 |
| 75    | 1/28/22 | 76    | 2/24/24 |
| 76    | 1/28/22 | 77    | 2/24/24 |
| 77    | 1/28/22 | 78    | 2/24/24 |
| 78    | 1/28/22 | 79    | 2/24/24 |
| 79    | 1/28/22 | 80    | 2/24/24 |
| 80    | 1/28/22 | 81    | 2/24/24 |
| 81    | 1/28/22 | 82    | 2/24/24 |
| 82    | 1/28/22 | 83    | 2/24/24 |
| 83    | 1/28/22 | 84    | 2/24/24 |
| 84    | 1/28/22 | 85    | 2/24/24 |
| 85    | 1/28/22 | 86    | 2/24/24 |
| 86    | 1/28/22 | 87    | 2/24/24 |
| 87    | 1/28/22 | 88    | 2/24/24 |
| 88    | 1/28/22 | 89    | 2/24/24 |
| 89    | 1/28/22 | 90    | 2/24/24 |
| 90    | 1/28/22 | 91    | 2/24/24 |
| 91    | 1/28/22 | 92    | 2/24/24 |
| 92    | 1/28/22 | 93    | 2/24/24 |
| 93    | 1/28/22 | 94    | 2/24/24 |
| 94    | 1/28/22 | 95    | 2/24/24 |
| 95    | 1/28/22 | 96    | 2/24/24 |
| 96    | 1/28/22 | 97    | 2/24/24 |
| 97    | 1/28/22 | 98    | 2/24/24 |
| 98    | 1/28/22 | 99    | 2/24/24 |
| 99    | 1/28/22 | 100   | 2/24/24 |

**QuickBOLT**  
World's First UL Certified Microflashing®  
5830 LAS POSITAS RD PH: (844) 671-6045  
LIVERMORE, CA 94551 WWW.QUICKBOLT.COM




PRODUCT:  
QB2 KIT WITH  
SS L-FOOT AND  
MICROFLASHING  
DWG: QB2HVHZ  
SHEET: 1/2


**QB2 ANCHOR BRACKET SYSTEM  
WITH 3" MICROFLASHING.**



**PART# 17661 – QB2 L-FOOT  
BRACKET. (304 SERIES  
STAINLESS STEEL).**



**PART# 17669 – 3" MICROFLASHING.  
3"  $\phi$  x 0.029" STAINLESS STEEL  
(304 SERIES) WASHER, WITH  
2 7/8"  $\phi$  x 0.131" EPDM GASKET.**



**PART# 17660 – 5/16"x4"  
STAINLESS STEEL (304 SERIES)  
HEX FLANGE DUAL DRIVE WOOD  
SCREW.**

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. **24-0306.05**  
Expiration Date **06/23/2027**  
By *[Signature]*  
Miami-Dade Product Control

PRODUCT:  
**QB2 KIT WITH  
SS L-FOOT AND  
3" MICROFLASHING**  
DWG:  
**QB2HVHZ**  
SHEET:  
**2/2**



**QuickBOLT**  
World's First UL Certified Microflashing®  
5830 LAS POSITAS RD  
LIVERMORE, CA 94551  
PH: (944) 671-6045  
WWW.QUICKBOLT.COM

| REV# | ISSUED FOR       | DATE    |
|------|------------------|---------|
| 1    | 2023 CODE UPDATE | 2/24/24 |
| 2    | 1ST SUBMITTAL    | 1/28/22 |

# FLORIDA APPROVAL LETTER



FL# 35022

December 8th, 2021

To whom this may concern,

QuickBOLT's strongest Top Mount, QB2, has been officially approved by the Florida Department of Business and Professional Regulations. Now that QB2 has been approved, solar installers in Florida can expect an even easier permitting process when submitting designs that include the QB2.

Florida is known for having notoriously high standards for building codes due to its High-Velocity Hurricane Zones (HVHZ), like in Miami Dade County. All new projects must meet a set of requirements to ensure products are secure when tested against these extreme weather conditions. Florida Product Approval Numbers (FL#) are the state measurement for these requirements. This approval requires going through a series of rigorous product evaluations.

QuickBOLT received its Florida Approval in January 2021 for their QB2 Kit with 3" Microflashing®, which mounts over asphalt shingle. Our Florida Approval included TAS 100(A) and Load Testing, which are the same tests required for Miami-Dade approval.

Regards,

Corrina Roberts  
Campaign Manager

# FLORIDA BUILDING CODE

## APPROVED APPLICANT PAGE

FLORIDA DEPARTMENT OF  
**Business & Professional Regulation**

**dbpr**  
Department of Business & Professional Regulation

OFFICE OF THE SECRETARY

BCIS Home | Log In | User Registration | Hot Topics | Submit Surcharge | Stats & Facts | Publications | Contact Us | BCIS Site Map | Links | Search

**Product Approval**  
USER: Public User

[Product Approval Menu](#) > **Application Detail**

FL #

Application Type

Code Version

Application Status

Comments

Archived

Product Manufacturer

Address/Phone/Email

Authorized Signature

Technical Representative

Address/Phone/Email

Quality Assurance Representative

Address/Phone/Email

Category

Subcategory

Compliance Method

Florida Engineer or Architect Name who developed the Evaluation Report

Florida License

Quality Assurance Entity

Quality Assurance Contract Expiration Date

Validated By

Certificate of Independence

Referenced Standard and Year (of Standard)

Equivalence of Product Standards

Certified By

Sections from the Code

Product Approval Method

Date Submitted

Date Validated

Date Pending FBC Approval

Date Approved

FL35022

New

2020

Approved

☐

QuickBolt - A Division of Quickscrews, Inc.  
5830 Las Positas Road  
Livermore, CA 94551  
(925) 371-8215  
gwiener@quickscrews.com

Greg Wiener  
gwiener@quickscrews.com

Structural Components

Anchors

Evaluation Report from a Florida Registered Architect or a Licensed Florida Professional Engineer  
☐ Evaluation Report - Hardcopy Received

Scott Wolters

PE-62354

Intertek Testing Services NA, Inc. - QA Entity

12/31/2023

Lucas A. Turner, P.E., MBA

☒ Validation Checklist - Hardcopy Received

[FL35022\\_R0\\_COI\\_QB2\\_COI.pdf](#)

| Standard   | Year |
|------------|------|
| ASTM D7147 | 2011 |
| TAS 100(A) | 1995 |

Method 1 Option D

10/24/2020

10/26/2020

11/01/2020

12/16/2020

**Summary of Products**

| FL #                                                                                                                                                                                                                       | Model, Number or Name     | Description                                                                                                                                                                                                                                                                                                                             |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 35022.1                                                                                                                                                                                                                    | QB2 Anchor Bracket System | Solar Anchor Bracket with 3" Microflashing.                                                                                                                                                                                                                                                                                             |
| <b>Limits of Use</b><br>Approved for use in HVHZ: Yes<br>Approved for use outside HVHZ: Yes<br>Impact Resistant: N/A<br>Design Pressure: N/A<br>Other: Please see Installation Drawings and Eval Report for Limits of Use. |                           | <b>Installation Instructions</b><br><a href="#">FL35022_R0_II_Q_Install.pdf</a><br><a href="#">FL35022_R0_II_QB2_Dwg.pdf</a><br>Verified By: Scott Wolters FLPE# 62394<br>Created by Independent Third Party: Yes<br><b>Evaluation Reports</b><br><a href="#">FL35022_R0_AE_QB2_Eval.pdf</a><br>Created by Independent Third Party: Yes |

# FLORIDA PRODUCT EVALUATION

## WOLTERS ENGINEERING

ENGINEERING, DRAFTING, CONSULTING

15211 97<sup>th</sup> Road N  
West Palm Beach, FL 33412  
Ph/Fx: (561) 225-1982

### PRODUCT EVALUATION

PRODUCT: QB2 ANCHOR BRACKET SYSTEM WITH 3" MICROFLASHING

MANUFACTURER: QUICKBOLT – A DIVISION OF QUICKSCREWS INC.  
5830 LAS POSITAS ROAD  
LIVERMORE, CA 94551

To all concerned,

The QB2 Anchor Bracket System with 3" Microflashing, manufactured by Quickbolt, has been tested per ASTM D7147 and TAS 100(A) by Intertek B&C, with results shown in test reports K8370.01-301-18-R0 and K8370.02-301-18-R0. This anchor bracket system meets all of the requirements of 7<sup>th</sup> Edition (2020) Florida Building Code, including the HVHZ provisions.

#### Technical Documentation:

1. Drawing "QB2HVHZ" dated 10/5/20, signed and sealed by Scott Wolters, PE.
2. Test Reports listed above by Intertek B&C, signed and sealed by Tyler Westerling, PE
3. Supplemental Calculations to support "QB2HVHZ" drawing, signed and sealed by Scott Wolters, PE.

I have reviewed this submittal per the requirements of FAC Product Approval Rule Chapter 61G20-3.005 (4). Based on the limitations listed below and those provided in the documents above, this product meets all the requirements of the 7<sup>th</sup> Edition (2020) Florida Building Code generally, and chapter 15 specifically, including the HVHZ provisions.

Limitations: This Roof System is approved for use inside and outside of the HVHZ.

|                                   |                         |         |
|-----------------------------------|-------------------------|---------|
| <u>Max Allowable Loads (ASD):</u> | Direct Tension (F1):    | 709 lb. |
|                                   | Strong Axis Shear (F2): | 237 lb. |
|                                   | Weak Axis Shear (F3):   | 29 lb.  |

|                                                            |                 |          |
|------------------------------------------------------------|-----------------|----------|
| <u>Bracket Dimensions:</u><br>(304 Series Stainless Steel) | Min. Thickness: | 0.158 in |
|                                                            | Min Width:      | 1.575 in |
|                                                            | Max. Height:    | 3.347 in |

|                       |                                                |
|-----------------------|------------------------------------------------|
| <u>Min. Fastener:</u> | 5/16" x 4" 304 Series SS Hex Flange Wood Screw |
|-----------------------|------------------------------------------------|

*SPECIALIZING IN IMPACT RESISTANT CURTAINWALLS, STOREFRONTS, & WINDOWS*

Flashing:

3" Microflashing, made from 3"x.0.29" 304 Series SS Washer  
with 2 7/8" x 0.131" EPDM Gasket

Other Limitations:

1. Fire classification is not a part of this evaluation. Refer to a current Approved Roofing Materials Directory for fire ratings of this product.
2. Design of substrate is by others and is not a part of this evaluation.
3. Existing roofing is not a part of this evaluation.

If you have any questions or need more information concerning this approval, please contact me.

Thank you,

  
Scott Wolters  
FL PE# 62354  
OCT 23 2020



---

SPECIALIZING IN IMPACT RESISTANT CURTAIN WALLS, STOREFRONTS, & WINDOWS